

## MODEL HP 3200 HEAVY DUTY HIGH PROFILE TURNTABLE PLATFORM AUTOMATIC STRETCH WRAP SYSTEM GENERAL SPECIFICATIONS

PRODUCTION SPEED	<ul> <li>1-40 loads per hour NOTE: Process rates will vary with load size, number of wraps &amp; forklift load/unload time</li> </ul>
LOAD CAPACITY	<ul> <li>Maximum load weight: 4,500# dynamic – 10,000# static</li> <li>Maximum load size: 50" W x 50" L (71" max. load diagonal) x 80" H (plus up to 4" top overlap)</li> <li>Minimum load size: 30" W x 30" L x 24" H</li> </ul>
TURNTABLE	<ul> <li>52" octagonal 5/16" thick formed steel plate turntable</li> <li>4 point caster support system</li> <li>Turntable height less than 12" from floor</li> <li>ANSI #50 direct chain drive c/w chain tensioner</li> <li>3-12 RPM rotational speed c/w soft start acceleration</li> <li>1/2 HP AC variable speed motor</li> <li>Final revolution deceleration and positive stop alignment</li> <li>Front &amp; back forklift ports for easy movement</li> </ul>
FILM CARRIAGE ELEVATOR	<ul> <li>1/2 HP AC variable speed motor</li> <li>ANSI #40 direct chain drive c/w shock dampener &amp; Anti-Fall Safety Device</li> <li>Maintenance free carriage guidance system</li> </ul>
FILM DELIVERY SYSTEM	<ul> <li>NEW Super Rapid Thread II ™ 20" capacity pre-stretch film carriage</li> <li>Special Film Threading Device – Uniquely orientates the sticky side of the film against the pre-stretch rollers <u>and</u> the inside of the load</li> <li>1/2 HP AC variable speed motor</li> <li>Fully electronic dynamic dancer corner compensation</li> </ul>

FILM DELIVERY SYSTEM continued	<ul> <li>33% to 313% fixed stretch capability</li> <li>Pre-stretch ratio variable using easy sprocket change</li> <li>Carriage Descent Obstruction Safety Shut-Off Device</li> <li>Rapid Thread ™ Safety Door with auto power cut-off switch</li> <li>Side mounted film carriage for operator convenience and safety</li> <li>Superior <i>film-to-roller</i> contact area</li> <li>Lifetime warranty on pre-stretch rollers</li> </ul>
AUTOMATION FEATURES	<ul> <li>*All Electric – No Pneumatics Required"</li> <li>Electro-mechanically actuated film clamp mechanism</li> <li>Electro-mechanically actuated film tail cut/wipe arm mechanism</li> <li>Ni-chrome impulse hot wire film cut off c/w automatic periodic cleaning cycle</li> </ul>
CONTROL FEATURES	<ul> <li>PANASONIC PLC with Touchscreen Operator Interface</li> <li>Power Off – On – Reset switch &amp; Power On indicator light</li> <li>Single button Auto Wrap Cycle Start/Pause</li> <li>Cycle Pause for applying top sheets</li> <li>Reinforce Wrap control for mid-wrapping</li> <li>Emergency Stop button</li> <li>Turntable Jog button</li> <li>Film Carriage Lower &amp; Raise buttons</li> <li>Film Clamp Open/Close button</li> <li>Film tension (Force-to-Load) control</li> <li>Separate film carriage raise &amp; lower speed controls</li> <li>Variable turntable speed control</li> <li>Triple beam auto load height sensing photo-eye, detects dark or shiny loads</li> <li>Separate 1 to 12 revolution top &amp; bottom wrap control</li> <li>Selectable Reduced Bottom Film Force parameter for wrapping bottom of load</li> <li>A – B – C Wrap Program selector with capability to input and store unique wrapping parameters for each program</li> <li>Wireless remote start/stop control – optional lanyard, pendant or pedestal control station available</li> <li>NEMA 12 control panel enclosure</li> <li>Non-proprietary UL/CSA approved components</li> </ul>

STRUCTURAL FEATURES	<ul> <li>All structural steel construction</li> <li>Forklift truck portable base structure design – lifting tubes included for front and rear access</li> <li>Structural steel tube machine tower with sheet metal covers</li> <li>Electro-static powder coated paint finish</li> </ul>
ELECTRICAL INPUT REQUIREMENTS	<ul> <li>115 Volts 1 Phase 60 Hz 15 Amps</li> </ul>